Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of Work: Supplying and Laying of various bituminous mixes for repair of potholes and Road cut Portions from established Hot Mix Plant of minimum 50/80 TPH capacity (In Fully working condition) including manufacturing, supplying and laying including the cost of all materials, machineries, labours, consumables etc complete for a period of 2 years in Yelahanka Division

Sl No	Description of Items	No	Unit	Rate	Amount
1	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading II Material PWD CSR 21-22 VOl 3 it. No 10.5 Page No 76 (as per Issue Rates Dated 01-01-2023)				
		1	Sqm	460.90	460.90
	Approved Rates	460.90			
2	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with 40 mm of Wet Mix Macadam and Bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading II Materialincluding all lead, lift and cost of materialsandlabouretc.,complete				
		1	Sqm	415.72	415.72
	Approved Rates	415.72			
3	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with 100 mm of Wet Mix Macadam and Bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading II Material including all lead, lift and cost of materialsandlabouretc.,complete				
		1	Sqm	561.99	561.99
	Approved Rates	561.99			

Scanned with ACE Scanner

Description of Items	No	Unit	Rate	Amount
Total No of Wards	4			
Total No of Roads	2719			
Total Length of road in KM	428.35			
Total No of roads comes under DLP	890.00			
Total No of roads comes under NON- DLP	1829.00			
Total Amount Allocated for Each Ward				**1500000.00**
Total Amount Allocated for 4 Ward				**6000000.00**
Rupees in words : Sixty Laksh (including 18% GST)				

Certificate

1. The Quantity should be Asseseed based on the BBMP Fix My Street Application App.

2. The workspot was inspected and works is found to be necessary.

3. The area comes within the Bruhat Bangalore Mahanagara Palike limits.

4. The rates adopted based on the PWD SR,Bangalore circle for year 2021-2022, and Approved Rates.

Ramanjeneel

Asst. Executive Engineer
Yelahanka Sub. Divisor
(BBMP Ynk. Zn)
Yelahanka, Bangalore

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 5600

Scanned with ACE Scanner